ПРОЕКТНА СТОЙНОСТ НА ПРЕДЛОЖЕНОТО КОНКУРСНО РЕШЕНИЕ За идеен проект за Нова визия на Градския пазар в град Пазарджик	VALUE OF THE PROPOSED COMPETITION SOLUTION for conceptual design of the New Vision for the City Market - Pazardzhik
Обща стойност на реализация на проекта:	Total project realization value:
……ЛЕВА	……**8,225,000**……BGN

PROJECT REALIZATION VALUE BREAKDOWN				
ITEM	**QUANTITY**		**ITEM**	**QUANTITY**
CANOPY			**TRADING PAVILIONS**	
ENGINEERED TIMBER COLUMNS 300mm DIA.	68		CLT PANELS 200MM	838 SM
GLULAM 60mm X 200mm X 5700mm	1020		CLT PANELS 400MM	1038 SM
GLULAM 60mm X 200mm X 7700mm	816		CONCRETE STRIP FOOTINGS AND SLABS	207 M3
GLULAM 80mm X 400mm X 7700mm	136		BRICK	828 SM
GLULAM 80mm X 400mm X 5860mm	136		INTENSIVE GREEN ROOF	1038 SM
CONCRETE FOOTINGS 1000mm DIA. X 2500mm	68		STOREFRONT AND SIGNAGE	396 SM
STEEL KNIFE-PLATE HOLD DOWN	136		LIGHTING AND MEP	1038 SM
STEEL CAPITOL / BRACKETS	68		FLOWER STALLS	20
STEEL CABLES AND HARDWARE	272		**TRADING PAVILIONS TOTAL COST ESTIMATE**	**2,800,000 BGN**
STEEL CORNER BRACKETS	272			
PVC MEMBRANE AND FIXINGS	3196 SM		**SITE IMPROVEMENTS**	
LIGHTING AND MEP	3196 SM		PAVING- PEDESTRIAN	4332 SM
DRAINAGE	3296 SM		PAVING- PARKING	1734 SM
CANOPY TOTAL COST ESTIMATE	**4,175,000 BGN**		LANDSCAPING INCLUDING NEW TREES	1230 SM
			SEATING AND OTHER FURNITURE	55
OPEN AIR TABLES			SITE LIGHTING	4332 SM
RECLAIMED WOOD	450 SM		SITE DRAINAGE	4332 SM
CORUGATED METAL FEED TUBS	150		UTILITY CONNECTIONS	
OPEN AIR TABLES TOTAL COST ESTIMATE	**250,000 BGN**		**SITE IMPROVEMENTS TOTAL COST ESTIMATE**	**1,000,000 BGN**
			TOTAL PROJECT REALIZATION ESTIMATE	**8,225,000 BGN**